

Contact person Christian Larsson Building Technology and Mechanics +46 10 516 57 61 Christian.Larsson@sp.se

Reference 2011-06-23 PX14335F 1(3)

Formenta International AB Box 525 331 25 VÄRNAMO

# **Testing of flagpole**

#### 1 Introduction

By commission of Formenta International AB a bending test of a flagpole was performed.

Test place:

Formenta International test site in Värnamo, Sweden.

#### 2 Test object

Designation:

Flagpole "12m Original" made of glass-fibre reinforced polyester.

11.88 m Height 135 mm Diameter at base Diameter at top 63 mm Weight total 38.8 kg

Weight of bottom steel plate

and inner steel tube 12.8 kg Weight of flagpole 26.0 kg

The flagpole was, according to the client, reinforced with 4 layers oriented glass-fibre rowing 810 gr/m<sup>2</sup> unidirectional 80/20 and 2 layers

glass-fibre matte 300 gr/m<sup>2</sup>.

Selection of test objects:

The test objects have been selected by the client without SP's

assistance.

### 3 Test method and implement

Test method: The flagpole was tested with a force attached perpendicular to the top.

> The force was increased until rupture occurred. The force was measured with a load cell connected to a computer with the sampling rate of 1000 Hz. After the test a calculation of the bending moment in the bottom part of the flagpole was performed. An equally, over the whole length of the flagpole, distributed force giving the same bending moment at the bottom of the pole was then calculated. This equally distributed force was translated to a wind speed. The calculations are presented in the test

> > This document may not be reproduced other than in full, except with the

results.

Measurements:

Maximum load was registered.

Test date:

15 June, 2011.

### SP Technical Research Institute of Sweden

Borås

Postal address SP

Box 857

SE-501 15 BORÅS Sweden

Office location Västeråsen Brinellgatan 4

Phone / Fax / E-mail +46 10 516 50 00 +46 33 13 55 02

info@sp.se

prior written approval of SP.



## 4 Test results

The flagpole broke in 5 pieces at a force at the top of 1053 N. The orientation of the ruptures were 1.10 m, 2.49 m, 4.79 m and 8.49 m from the base and the top of the pole was when it broke bent approximately 7.8 m.

Following calculations are performed in accordance with the Swedish Building requirement for calculation of wind load.

Calculation of bending moment generated from a force attached to the top of the pole.

h = Height of pole, m.

 $F_h$  = Breaking force N.

$$M_v = F_h \times h = 1053 \text{ x } 11.88 = 12510 \text{ Nm}$$

Calculation of an equally distributed force generating same bending moment at the base of the pole.

 $d_b$  = Diameter at base of pole, m.

 $d_h$  = Diameter at top of pole, m.

L = Distance from base to the projected centre of area.

$$L = \frac{h (d_b + 2d_h)}{3(d_h + d_h)} = \frac{11.88 (0.135 + 2 \times 0.063)}{3 (0.135 + 0.063)} = 5.22m$$

$$F = \frac{M_v}{L} = \frac{12510}{5.22} = 2397 \text{ N}$$

Calculation of wind pressure

 $\varphi$  = Density of air at ambient temperature, kg/ m<sup>3</sup> = 1.25 kg/ m<sup>3</sup>

v = Wind speed, m/s

F = Force equally distributed over the projected area, 2397 N.

 $C_f$  = Factor cylindrical shape = 1.2.

A = Projected area, =  $\underline{d_{b+}}\underline{d_h} \times h$ ,  $m^2$ 

 $q = Wind pressure, N/m^2$ .

$$\mathbf{F} = \mathbf{C}_{\mathbf{f}} \times \mathbf{q} \times \mathbf{A}$$

$$q = \frac{F}{C_f \times A} = \frac{2 \times 2397}{1.2 \times 11.88 (0.063 + 0.135)} = 1698 \text{ N/m}^2$$



Calculation of wind speed

$$q = 0.5 \times \phi \times v^2$$

$$v^2 = \frac{q}{0.5 \text{ x } 1.25} = \frac{1698}{0.5 \text{ x } 1.25} = 2717$$

$$v = 52 \text{ m/s}$$

The breaking force of the flagpole corresponds approximately to a maximum wind speed of 52 m/s. Effects from flag and flag-line are considered being minor and are not taken into consideration in the calculations. The fact that the flagpole is bending because of the wind pressure and the projected area because of this is becoming lesser is also not taken into consideration.

# 5 Measurement uncertainty

The total calculated measurement uncertainty for the maximum load is < 1 %. Reported uncertainty corresponds to an approximate 95 % confidence interval around the measured value. The interval has been calculated in accordance with GUM (The ISO guide to the expression of uncertainty in measurements), which is normally accomplished by quadratic addition of the actual standard uncertainties and multiplication of the resulting combined standard uncertainty by the coverage factor k=2.

SP Technical Research Institute of Sweden Building Technology and Mechanics - Solid Mechanics and Structures

Performed by

Christian Larsson

Opristren Lergen

Examined by

Lars Andersson